	Biomedical Limited, No 1 Ohimege Road, Industrial Estate, Ilorin Kwara State, PMB 1449			MASTER COPY STAMP HERE
	Title: **Standard Operating Procedure For putting ON and putting OFF the FFU in a cascaded Environment**			
Department	**Unit**	**BML-ENG-NG-006**	**Revision No.:**	01
			Effective Date:	**April, 2025**
ENGINEERING	ENGINEERING GENERAL		**Next Review Date:**	**March, 2027**
Prepared By:	**Checked By:**		**Approved By:**	
sign/date	**sign/date**		**sign/date**	

1.0 PURPOSE: This SOP established the procedure for putting ON and OFF Fan Filter Unit in cascaded Environment

2.0 SCOPE: This SOP applies to all trained and qualified biomedical limited staffs and contractors operating the clean room FFU.

3.0 RESPONSIBILITY/ACCOUNTABILITIES:

- It is the responsibility of any qualified personnel
- It is the responsibility of Biomedical Limited to provide the PPE for the qualified employee performing the task
- It is the responsibility of contactors to provide the PPE for their qualified staff

It is the responsibility of the Engineering head to ensure that the SOP is strictly followed

4.0 POTENTIAL RISK: Shock, burn

5.0 PROCEDURE:

TO OFF THE FAN FILTER UNIT

- The fan filter unit inside the clean room with low pressure settings or with lower classification will be put OFF first. This is to prevent cross contamination from the room with lesser pressure or lower classification into the room with the higher pressure or higher classifications

TO ON THE FAN FILTER UNIT

- The fan filter unit in the clean room with high pressure settings or with higher classifications will be put ON first. This is to prevent cross contamination from the room with lesser pressure or lower classification into the room with the higher pressure or higher classifications

6.0 REFERENCES AND ENCLOSURE:

- Nil

7.0 TRAINING INVOLVEMENT:

All Engineering staff
All machine Operators

8.0 DISTRIBUTION AND CONTROL COPY:

- This is the various department/section where the SOP copies will be utilized.

MASTER COPY	QUALITY
CONTROLLED COPY	QUALITY, ENGINEERING, PRODUCTION

9.0 CHANGE HISTORY:

CURRENT REVISION	SUPERSEDE	REASON FOR REVIEW
00	Nil	First issue
01	00	• Change in sop format. • Inclusion of traceability of enclosures to parent SOP